

CPCS Categories

Code	Description	Endorsement A	Endorsement B	Endorsement C	Endorsement D	Training Duration
A02	Crawler Crane	Up to 10 tonnes	All sizes			70
A04	Tower Crane	Trolley Jib	Luffing Jib			70
A05	Dragline					70
A06	Truck-mounted Boom Concrete Pump					35
A09	Forward Tipping Dumper	Wheeled	Tracked			24
A10	Excavator 180° below 5 tonnes					70
A12	Excavator 180° above 5 tonnes					70
A14	Rough Terrain Forklift/Masted Truck					35
A15	Forklift Side-loader					35
A16	Industrial Forklift Truck					35
A17	Telescopic Handler	Industrial telescopic	Up to 9 metres	All sizes excluding 360° slew	All sizes including 360° slew	35
A18	Reach Truck					35
A19	Grader					70
A20	Hoist	Rack and Pinion Goods	Passenger/Goods combined	Rope-Operated Goods	Transport Platform	21
A21	Wheeled Loading Shovel					35
A22	Tracked Loading Shovel					70
A23	Skid Steer Loader					35
A24	Motorised Scraper					70
A25	Mobile Elevating Work Platform – Scissor					21
A26	Mobile Elevating Work Platform – Boom	Vehicle-mounted	Self-propelled			21

A27	Mobile Elevating Work Platform – Mast Climber					21
A30	Piling Rig – Tripod					28
A31	Ride-on Roller					28
A32	Soil-Landfill Compactor					35
A33	Agricultural Tractor					28
A34	Crawler – Tractor/Dozer					70
A35	Crawler – Tractor/Side Boom					35
A36	Lorry Loader	Hook	Clamshell Bucket	Hydraulic Clamp		35
A37	Trencher					28
A39	Skip Handler					28
A40	Slinger/Signaller					28
A41	Loader-Compressor					28
A42	Crusher					28
A43	Screener					28
A44	Trailer-mounted Concrete Pump					28
A45	Piling Rig – Driven below 15 tonnes					70
A46	Piling Rig – Driven above 15 tonnes					70
A47	Piling Rig – Bored below 15 tonnes					70
A48	Piling Rig – Bored above 15 tonnes					70
A49	Loader/Securer – non-STGO	Non-LGV	LGV			42
A50	Plant Loader/Securer – STGO					42
A51	Road/Rail Excavator	Discontinued 1/04/05 – See Road/Rail Plant Matrix				
A52	Road/Rail Excavator/Crane	Discontinued 1/04/05 – See Road/Rail Plant Matrix				
A53	Demolition Plant – Non-hydraulic	Scheduled to be replaced (see A65)				70
A54	Demolition Plant – Hydraulic Rotating	Scheduled to be replaced (see A65)				70

A55	Demolition Plant – Long Reach	Scheduled to be replaced (see A65)				70
A56	Dump Truck – Articulated Chassis	Up to 15 tonnes	All sizes			35
A57	Dump Truck – Rigid Chassis	Up to 15 tonnes	Up to 50 tonnes	All sizes (wheeled)	Tracked	35
A58	Excavator 360° below 10 tonnes	Tracked	Wheeled			70
A59	Excavator 360° above 10 tonnes	Tracked	Wheeled			70
A60	Mobile Crane	Blocked duties only	Pick and carry duties only	All duties		70
A61	Appointed Person (Lifting Operations)					TBA
A62	Crane Supervisor (Lifting Operations)					TBA
A63	Pedestrian Operated Tower Crane	Up to 36m –100m/te	Inclined Jib			42
A64	Overhead Bridge Crane – Track					TBA
A65	Demolition Plant	Materials Processing	Non-hydraulic	Hydraulic rotating	High Reach	70